

 GOVERNMENT OF DUBAI	Organization/Unit:	إدارة مختبر دبي المركزي Dubai Central Laboratory Department	الوحدة التنظيمية:	 بلدية دبي DUBAI MUNICIPALITY
	Document Title:	Specific Rules for Certification of Slag Cement for use in Concrete and Mortars as per ASTM C989/C989M-18 Through Factory Assessment	عنوان الوثيقة:	
	Doc Ref.	DM-DCLD-RD-DP21-2212 (IC)	رقم الوثيقة :	

Issue Date	Rev. No.	Summary Of Amendments
08-05-2019	0	First draft for comments
11-06-2019	1	Issue for use
04-08-2020	2	Add the options for initial audit by the approved CAB and remotely by PCAS. Adding definition for authorized auditor. Update for the new numbering system and followed terminologies. Add provision for accepting valid test reports. Correction of numbering
26/09/2021	3	Revised to reflect the Removal of the documents in clause 2.1.2, in addition to further amendment in the provision for accepting valid test reports (clause 2.4.2.5), in line with DM 30% reduction of requirements (both service and specialized). Modifications in the auditing part for the factories already certified against ISO 9001 to opt for auditing only the areas of production and monitoring stages of product realization, quality control and final product testing and evaluation.

Approved by HOU	Authorized by PCASM
Date of Issue : 26/09/2021	Rev. No. : 03
General / عام : Level of Confidentiality / درجة السرية	Page 1 of 9

Note: Printed copy of this document shall be treated as 'Uncontrolled'. Always refer the controlled version Online

OPEN DATA / بيانات مفتوحة

 GOVERNMENT OF DUBAI	Organization/Unit:	إدارة مختبر دبي المركزي Dubai Central Laboratory Department	الوحدة التنظيمية:	 بلدية دبي DUBAI MUNICIPALITY
	Document Title:	Specific Rules for Certification of Slag Cement for use in Concrete and Mortars as per ASTM C989/C989M-18 Through Factory Assessment	عنوان الوثيقة:	
	Doc Ref.	DM-DCLD-RD-DP21-2212 (IC)	رقم الوثيقة :	

1. GENERAL

1.1 INTRODUCTION

- 1.1.1 This document prescribes the specific rules for the implementation of the DM Third Party Product Certification Scheme Through Factory Assessment as applied to the specific product(s) identified herein, taking into consideration the applicable normative references and standard specifications.
- 1.1.2 The applicant shall comply with these specific rules, and to those already mentioned in the “General Rules for DM Third Party Product Certification System Scheme Through Factory Assessment” DM-DCLD-RD-DP21-2001 (IC).

1.2 SCOPE

This specific rule applies to chemical and physical properties as well as quality control procedures for Slag cement that will be used in the production of concrete and mortar

1.3 PRODUCT IDENTIFICATION AND APPLICABLE STANDARD/NORMATIVE REFERENCE

- 1.3.1 Product name: Slag Cement
- 1.3.2 Applicable Standard/Normative Reference: ASTM C989/C989M- 18 Standard Specification for Slag cement for use in Concrete and Mortars.
- 1.3.3 Additional References:
- ISO 9001 Quality Management System – Requirements
- ISO 19011 Guidelines for Auditing Management Systems

1.4 DEFINITION OF TERMS

In addition to the definitions given in the Applicable Standard specification (clause 3), Normative Reference, and DM-DCLD-RD-DP21-2001(IC) the following shall also apply:

- 1.4.1 Independent Testing Laboratory – Dubai Central Laboratory (DCL) or any testing laboratory recognized by DCLD-PCAS.

Approved by HOU	Authorized by PCASM
Date of Issue : 26/09/2021	Rev. No. : 03
General / عام : Level of Confidentiality / درجة السرية	Page 2 of 9

Note: Printed copy of this document shall be treated as 'Uncontrolled'. Always refer the controlled version Online

بيانات مفتوحة / OPEN DATA

 GOVERNMENT OF DUBAI	Organization/Unit:	إدارة مختبر دبي المركزي Dubai Central Laboratory Department	الوحدة التنظيمية:	 بلدية دبي DUBAI MUNICIPALITY
	Document Title:	Specific Rules for Certification of Slag Cement for use in Concrete and Mortars as per ASTM C989/C989M-18 Through Factory Assessment	عنوان الوثيقة:	
	Doc Ref.	DM-DCLD-RD-DP21-2212 (IC)	رقم الوثيقة :	

- 1.4.2 Independent Test – test performed or conducted by the recognized Independent Testing Laboratory
- 1.4.3 Standard Specification – ASTM C989/C989M, Standard Specification for Slag cement for use in Concrete and Mortars
- 1.4.4 Product Quality Assurance Plan – a document being agreed upon both by the client and the DCLD-PCAS, being used to ensure continuous compliance of the certified product.
- 1.4.5 QMS – Quality Management System aligned with the requirements of ISO 9001 Standard
- 1.4.6 Client – Manufacturer of Slag Cement for use in Concrete and Mortars
- 1.4.7 DM Certification Body: Dubai Central Laboratory Department-Products Conformity Assessment Section (DCLD-PCAS)
- 1.4.8 Authorized auditor : is any approved auditor by DCLD-PCAS either internal within DCLD or external (Approved CAB's auditor or approved auditor based on a signed contract)

2. REQUIREMENTS FOR CERTIFICATION

2.1 APPLICATION

- 2.1.1 The client shall apply to DCLD-PCAS for the Certification and authorization to use the DCL Conformity Mark.
- 2.1.2 Application forms shall be submitted by client to DCLD-PCAS.
- 2.1.3 Separate application shall be submitted for each product type or group of products that refers to a different specific rules.

2.2 FACTORY OPERATION

2.2.1 Quality Management System

The client shall have a Quality Management System that is aligned to the requirements of ISO 9001 standard.

NOTE : Having a certificate of ISO 9001 is not a mandatory requirement; however the structure of the manufacturer's QMS shall be in line with its requirements.

Approved by HOU	Authorized by PCASM
Date of Issue : 26/09/2021	Rev. No. : 03
General / عام : Level of Confidentiality / درجة السرية	Page 3 of 9

Note: Printed copy of this document shall be treated as 'Uncontrolled'. Always refer the controlled version Online

بيانات مفتوحة / OPEN DATA

 GOVERNMENT OF DUBAI	Organization/Unit:	إدارة مختبر دبي المركزي Dubai Central Laboratory Department	الوحدة التنظيمية:	 بلدية دبي DUBAI MUNICIPALITY
	Document Title:	Specific Rules for Certification of Slag Cement for use in Concrete and Mortars as per ASTM C989/C989M-18 Through Factory Assessment	عنوان الوثيقة:	
	Doc Ref.	DM-DCLD-RD-DP21-2212 (IC)	رقم الوثيقة :	

2.2.2 Laboratory

The client shall have a quality assurance laboratory to carry out factory production control testing to ensure that the Slag cement products comply with the requirements of the standard specification.

The laboratory can be part of the factory facilities, or, can be through a documented agreement with an accredited external laboratory. As a minimum requirement, the factory shall have the following minimum test equipment to check product compliance with the requirements of standard specification.

1. Compression machine
2. Digital & weighing balances
3. Water bath and hot plate
4. Drying oven & Muffle furnace
5. Mortar mixer
6. Humidity cabinet & Thermo hygrometer
7. Chemical analyzer (Online or portable XRF) and/or Wet chemistry instruments.
8. Soundness and setting time.
9. Blaine fineness apparatus

2.2.3 Classification :

Slag Cement is classified by performance in the slag activity test in three grades : Grade 80 , Grade 100 and Grade 120 (please refer to table 1) in the standard

2.3 INITIAL FACTORY AUDIT

- 2.3.1 Initial factory audit will be carried out by duly authorized auditor(s) which will cover auditing of the quality management system to verify its compliance with the requirements of ISO 9001, in addition to verify the implementation of DCLD-PCAS certification's requirements. Where possible; the audit can be carried out remotely as per (DM-DCLD-RD-DP21-2098 (IC) Guidelines for Remote Audit) or as per the related approved guidelines which are followed by the approved outsourced CAB.

NOTE: An independent certification to ISO 9001 issued by a QMS certification body recognized by DCLD-PCAS may be considered as having satisfied this requirement; however, DCLD-PCAS may still opt to carry out verification audit to confirm that the factory is in compliance with requirements of DCLD certification schemes and rules, mainly the areas of production and monitoring stages of product realization, quality control and final product testing and evaluation.

Approved by HOU	Authorized by PCASM
Date of Issue : 26/09/2021	Rev. No. : 03
General / عام : Level of Confidentiality / درجة السرية	Page 4 of 9

Note: Printed copy of this document shall be treated as 'Uncontrolled'. Always refer the controlled version Online

OPEN DATA / بيانات مفتوحة

 GOVERNMENT OF DUBAI	Organization/Unit:	إدارة مختبر دبي المركزي Dubai Central Laboratory Department	الوحدة التنظيمية:	 بلدية دبي DUBAI MUNICIPALITY
	Document Title:	Specific Rules for Certification of Slag Cement for use in Concrete and Mortars as per ASTM C989/C989M-18 Through Factory Assessment	عنوان الوثيقة:	
	Doc Ref.	DM-DCLD-RD-DP21-2212 (IC)	رقم الوثيقة :	

2.3.1 Factory audit shall be conducted by designated audit team in accordance with ISO 19011 – Guidelines for Auditing Management Systems.

2.4 PRODUCT EVALUATION

2.4.1 Sampling

2.4.1.1 Sampling for initial testing shall be taken randomly by the authorized auditor from the products to be certified (sizes and quantity to be determined) either from production lines or the factory warehouse, in accordance with the requirements of ASTM C390.

2.4.1.2 Three sets of sample per product per type should be selected – as applicable from the production line or from the warehouse and shall be subjected to testing; the first set, where possible, will be tested in the plant witnessed by a duly authorized auditor, the second set will be sent to DCLD-PCAS approved Independent Testing Laboratory. The third set will be kept by the manufacturer as reference for future use.

2.4.1.3 Sample(s) for independent test shall be packed/sealed and signed in the presence of the authorized auditor and shall be submitted to DCLD-PCAS approved lab.

2.4.2 Product Evaluation and Testing

2.4.2.1 General Requirements:

Slag Cement covered by this specification shall comply with the minimum requirements as per clause 6 (additions) of the specification standard.

2.4.2.2 The compliance of the common comments with the requirements of this standard and the stated values (including classes) shall be demonstrated by :

- Initial type testing
- Factory production control by the manufacturer, including product assessment.

2.4.2.3 The physical properties of slag cement shall conform to the requirements of Table 1 in clause 8.0 of the standard specification.

2.4.2.4 The chemical composition of the slag cement shall conform to the requirements of Table 2 in clause 7.0 of the standard specification.

Approved by HOU	Authorized by PCASM
Date of Issue : 26/09/2021	Rev. No. : 03
General / عام : Level of Confidentiality / درجة السرية	Page 5 of 9

Note: Printed copy of this document shall be treated as 'Uncontrolled'. Always refer the controlled version Online

بيانات مفتوحة / OPEN DATA

 GOVERNMENT OF DUBAI	Organization/Unit:	إدارة مختبر دبي المركزي Dubai Central Laboratory Department	الوحدة التنظيمية:	 بلدية دبي DUBAI MUNICIPALITY
	Document Title:	Specific Rules for Certification of Slag Cement for use in Concrete and Mortars as per ASTM C989/C989M-18 Through Factory Assessment	عنوان الوثيقة:	
	Doc Ref.	DM-DCLD-RD-DP21-2212 (IC)	رقم الوثيقة :	

- 2.4.2.5 Where applicable, independent test should only be conducted if the result of the in-plant test shows satisfactory result. DCLD-PCAS shall accept available valid test reports conducted by an approved DCLD-PCAS independent laboratory within one year from the date of the initial assessment, in line with the internal quality control testing plan of the factory. In such case, the testing of that particular parameter(s) shall be waived accordingly.
- 2.4.2.6 The performance testing procedures and methods shall be according to clause 10.0 of the standard specification
- 2.4.2.7 Factory production control (Inspection testing plan ITP) for product testing and evaluation (frequency and volume) shall be made by applicant and submitted for DCL review
- 2.4.2.8 The Rejection and rehearing shall be according to the requirements of clause 11.0 of the specification standard
- 2.4.2.9 Marking and labeling shall be according to clause 14.0 of the standard specification.
- 2.4.2.10 Storage shall be maintained in accordance with the minimum requirements of clause 15.0 of the standard Specification.
- 2.4.2.11 The results of testing must meet the requirements as per the standard specification.
- 2.4.2.12 If the result of the test conducted by the DCLD-PCAS approved independent testing laboratory shows non-conformance to the specified requirements, the provision for rejection specified in the standard shall apply. The retest shall be carried out on the reference sample kept by the manufacturer or on new samples collected by the authorized auditor on which full testing shall be carried out ,if necessary.

3. GRANTING OF THE DCL CERTIFICATION

3.1 CONDITIONS FOR GRANTING THE DCL PRODUCT CONFORMITY CERTIFICATE

- 3.1.1 When the results of the factory audit (clause 2.3) and product evaluation (clause 2.4) show conformity to the requirements specified in the general rule and specific rule, the Certificate of Conformity and authorization to use the DCL Conformity Mark shall be issued to the client for the type(s)/model(s)/brand(s) of the product covered by the assessment.

Approved by HOU	Authorized by PCASM
Date of Issue : 26/09/2021	Rev. No. : 03
General / عام : Level of Confidentiality / درجة السرية	Page 6 of 9

Note: Printed copy of this document shall be treated as 'Uncontrolled'. Always refer the controlled version Online

بيانات مفتوحة / OPEN DATA

 GOVERNMENT OF DUBAI	Organization/Unit:	إدارة مختبر دبي المركزي Dubai Central Laboratory Department	الوحدة التنظيمية:	 بلدية دبي DUBAI MUNICIPALITY
	Document Title:	Specific Rules for Certification of Slag Cement for use in Concrete and Mortars as per ASTM C989/C989M-18 Through Factory Assessment	عنوان الوثيقة:	
	Doc Ref.	DM-DCLD-RD-DP21-2212 (IC)	رقم الوثيقة :	

3.1.2 The client shall agree with DCLD-PCAS for the preparation and implementation of a product quality assurance plan / mechanism to ensure continuing compliance with the Standard Specifications and the requirements of this certification scheme. It shall consist of (1) an internal product quality assurance plan, and (2) an independent testing plan.

3.1.3 Factory Production Control System (Internal Product Quality Assurance Plan)

The client shall have an internal product quality assurance plan giving details of the tests to be carried out at the factory. This will include as a minimum, the following details: (1) location of sampling; (2) frequency of sampling; (3) quantities of samples; (4) tests to be carried out; (5) results acceptance criteria; and (6) responsible person to carry out the activity. The plan shall cover all inspections carried out thru out the whole manufacturing process; i.e. (raw materials – production lines- finished product testing and evaluation as per standard specifications –final packing.

The plan shall take into consideration the production process, the volume of production, the criticality of the test to be specified, and other relevant factors

3.1.4 Independent testing plan

The client shall agree to an independent testing plan to be carried out on samples which are collected in accordance with DM-DCLD-RD-DP21-2096 (IC) – Surveillance of Certified Clients under the Factory Assessment Scheme, and implemented by DCLD-PCAS.

3.2 ISSUANCE OF DCL CERTIFICATE OF CONFORMITY

If the conditions mentioned in clause 3.1 above have been complied, the client shall be issued a DCL Certificate of Conformity and a Scope of Certification that covers the type(s) and size of the products that are certified and will be authorized to use the DCL Conformity Mark on the certified products.

3.3 RESPONSIBILITIES OF THE CERTIFIED CLIENT

3.3.1 The client shall ensure that his product, for which a certificate of conformity has been issued, conforms at all times to the requirements of the General Rule and Specific Rules, and regulations and legislation, whenever applicable, and shall maintain to the satisfaction of DCLD-PCAS, a system of quality control including inspection and testing.

3.3.2 The client shall give the duly authorized auditor(s), access during working hours, without prior notification, to the premises of the factory where certified product is manufactured, for the purpose of evaluating the

Approved by HOU	Authorized by PCASM
Date of Issue : 26/09/2021	Rev. No. : 03
General / عام : Level of Confidentiality / درجة السرية	Page 7 of 9

Note: Printed copy of this document shall be treated as 'Uncontrolled'. Always refer the controlled version Online

OPEN DATA / بيانات مفتوحة

 GOVERNMENT OF DUBAI	Organization/Unit:	إدارة مختبر دبي المركزي Dubai Central Laboratory Department	الوحدة التنظيمية:	 بلدية دبي DUBAI MUNICIPALITY
	Document Title:	Specific Rules for Certification of Slag Cement for use in Concrete and Mortars as per ASTM C989/C989M-18 Through Factory Assessment	عنوان الوثيقة:	
	Doc Ref.	DM-DCLD-RD-DP21-2212 (IC)	رقم الوثيقة :	

materials, production processes, finished products, quality assurance facilities, records and others in accordance with the requirements of the scheme.

- 3.3.3 The client shall inform DCLD-PCAS in writing of any change of management, transfer of plant site, modification in the product, manufacturing process or factory's quality management system.
- 3.3.4 Upon transfer of plant site, the certificate of conformity shall be deemed valid only after factory and product audit at the new site has been satisfactorily completed.
- 3.3.5 Any infraction stated in the terms and conditions of the certification scheme and the use of DCL Conformity Mark shall constitute sufficient grounds for suspension, withdrawal and termination of certification in accordance with DM-DCLD-IMS-RD-07.
- 3.3.6 Any dispute that may arise in connection with the Terms and Conditions of the certification scheme shall be settled in accordance with DM-DCLD-IMS-RD-08 Appeals, Disputes, and Complaints Procedure.
- 3.3.1 The client shall pay all applicable fees related to the certification process.
- 3.4 USE OF THE DCL CONFORMITY MARK
- 3.4.1 The design and use of the DCL Conformity Mark shall be in accordance with the Terms and Conditions for the Use of the DCL Conformity Mark, DM-DCLD-IMS-RD-13
- 3.4.2 The client shall submit a product-marking proposal for approval by DCLD-PCAS. The proposal shall include drawings and/or diagrams showing the location and size of the marking for each size of the product/product container, where applicable
- 3.4.3 The Certificate of Conformity and the authorization to use the DCL Conformity Mark is non-transferable.
4. SURVEILLANCE
- 4.1 DCLD-PCAS or their approved CAB shall carry out periodic surveillance to ensure consistent compliance with the requirements of this certification scheme as per DM-DCLD-RD-DP21-2096 (IC) – Surveillance of Certified Clients under the Factory Assessment Scheme.

Approved by HOU	Authorized by PCASM
Date of Issue : 26/09/2021	Rev. No. : 03
General / عام : Level of Confidentiality / درجة السرية	Page 8 of 9

Note: Printed copy of this document shall be treated as 'Uncontrolled'. Always refer the controlled version Online

بيانات مفتوحة / OPEN DATA

 GOVERNMENT OF DUBAI	Organization/Unit:	إدارة مختبر دبي المركزي Dubai Central Laboratory Department	الوحدة التنظيمية:	 بلدية دبي DUBAI MUNICIPALITY
	Document Title:	Specific Rules for Certification of Slag Cement for use in Concrete and Mortars as per ASTM C989/C989M-18 Through Factory Assessment	عنوان الوثيقة:	
	Doc Ref.	DM-DCLD-RD-DP21-2212 (IC)	رقم الوثيقة :	

- 4.2 Testing as part of the surveillance shall be in accordance with the Independent Testing Plan (clause 3.1.4) that has been agreed between DCLD-PCAS - and the client.

5. FEE SCHEDULE

- 5.1 The client shall pay the applicable fees and charges related to the granting of the certificate of conformity and the authorization to use the DCL Conformity Mark based on DCL Official Fee Structure, DM-DCLD-RD-DP21-2074(IC).
- 5.2 The fees for this certification scheme shall include but not limited to the following
- 5.2.1 Application Fee
 - 5.2.2 Initial Assessment Fee
 - 5.2.3 Certification Fee
 - 5.2.4 Marking Fee
 - 5.2.5 Surveillance Fee
 - 5.2.6 Annual Renewal Fee
 - 5.2.7 Testing Fee
 - 5.2.8 Outsource Activity Fee , where applicable

Approved by HOU	Authorized by PCASM
Date of Issue : 26/09/2021	Rev. No. : 03
General / عام : Level of Confidentiality / درجة السرية	Page 9 of 9

Note: Printed copy of this document shall be treated as 'Uncontrolled'. Always refer the controlled version Online

بيانات مفتوحة / OPEN DATA