

Circular No. (12-11-1) of 2023

Dated (11/08/2023)

Issued to all engineering consulting offices, and contracting companies operating in the Emirate of Dubai

On/ Providing security and guarding requirements and installing surveillance cameras at building sites under construction and demolition

Dubai Municipality is constantly keen to raise the level of application of security and safety requirements at construction sites in accordance with the Construction Works Safety Practice Guide approved by Dubai Municipality and the circulars issued in this regard. Therefore, all engineering consulting offices and contracting companies operating in the Emirate of Dubai are required to adhere to the following instructions at construction and demolition sites:

- Providing highly efficient security guards around the clock at the sites.
- Installing a sufficient number of surveillance cameras according to the nature and size of the project, and ensuring their continued validity and operation, preferably equipped with an alarm sensor if possible.
- Keeping construction materials, equipment, and devices in safe and suitable storage places within the sites.
- Providing adequate lighting at sites according to the size of the project.
- Using external fences for projects in accordance with the specifications contained in Circular No. (12-4-1) issued by the Municipality on 23/08/2021G, provided that they are securely installed and closed. Gates shall be installed to organize entry and exit traffic into and out from the projects.

- It is preferable to begin implementing the permanent external fences of the project in conjunction with the implementation of the main buildings and the installation of gates.
- For reports related to construction and demolition sites, please call (901), and for any other inquiries, please call (800900).

We hope that all parties will adhere to the content of this circular and act accordingly to serve the public interest.

“This is a technical translation, in case of ambiguity Arabic version will prevail “